



QE-EPTA 380/220V						
CIRCUITO	ILUMINAÇÃO(W)	TOMADAS(W)	CARGAS	TOTAL	DISJUNTOR	CONDUTOR
	2X18W	100 W	ESPECIAIS	W	A	mm ² - 1kV
1-ILUM. EQUIPAM	4			144	1x10	2x2,5
2-ILUM. SL AIS	6			216	1x10	2x2,5
3-ILUM. CIRCULAÇÃO	3			108	1x20	2x2,5
4-ILUM. SL AFIS/EMS	6			216	1x20	2x2,5
5- TOM. EQUIP. 01			2000		1x20	2x4,0
6- TOM. EQUIP. 02			2000		1x20	2x4,0
7- TOM. EQUIP. 03			2000		1x20	2x4,0
8- TOM. EQUIP. 04			2000		1x20	2x4,0
9- TOM. EQUIP. 05			2000		1x20	2x4,0
10- TOM. EQUIP. 06			2000		1x20	2x4,0
11- TOM. SL AIS		10		1000	1x20	2x4,0
12- TOM. SL AFIS		10		1000	1x20	2x4,0
13- TOM. SL EMS		5		500	1x20	2x4,0
14- TOM. CIRCULAÇÃO		2		200	1x20	2x4,0
15- AR COND. SL EQUIP.			994		1x20	2x4,0
16- AR COND. SL EQUIP.			994		1x20	2x4,0
17- AR COND. SL AIS			994		1x20	2x4,0
18- AR COND. SL AFIS			994		1x20	2x4,0
19- AR COND. SL EMS			994		1x20	2x4,0
					1x20	2x4,0
TOTAL				2014	3x50	4x16,0



SALA EPTA
ESC.: 1/25

00	07/12/2020	B	YURI	EMISSÃO INICIAL	
REV.	DATA	TIPO	POR	DESCRIÇÃO DAS REVISÕES	
EMISSIONS					
TYPE OF ISSUE		(A)PRELIMINARY (B)FOR APPROVAL	(C)FOR QUOTATION (D)FOR CONSTRUCTION	(E)CONFORMING TO BE BUILT (F)FINAL VERSION	
SAC/PR-BB-LOTE 00				 Traçado Engenharia Elétrica Consórcio Traçado-Engelétrica Reforma e ampliação Aeroporto de Passo Fundo	
RESPONSIBLE		DATE	TECHNICAL RESPONSIBLE		Nº CREA/CAU
APR. Eng. Fernando Derques Lopez		07/12/2020	Eng. Fernando Derques Lopez		CREA 51.060/RS
DES. Yuri Zacher		07/12/2020	SPECIALTY		
VER. Eng. Fernando Derques Lopez		07/12/2020	ELÉTRICA		
			CONTRACT Nº		039/2018
FISCAL		CREA/CAU	DATA	SIGNATURE	
PASSO FUNDO - RS - SBPF					
DESCRIPTION					
PROJECT ELECTRICAL LOW VOLTAGE EPTA					
SCALE	N.PROJ				NUM.
INDICADA	AER-PFB-ELR-EPTA-PE-01-PDF-R00				01 / 01
					REV.
					00
THIS PLANT ONLY WILL BE USED IF PLOTTED COLOR BY PART FROM A FILE IN PDF OR DWG FORMAT					
RESERVED RIGHTS AUTOMATICALLY					